

LISTA CANTITATI DE LUCRARI
Instalatii retele apa, canal si termoficare

1	DG06B1	Spargere si desfacere beton(90x0,8x0,2=14,4mc)	mc	14,4
2	DZ30K1	Turnare beton	mc	14,4
3	ACE05A1	Piesa de trecere etansa la trecerea prin pereti	buc	2
4	TSA04C1	Sapatura manuala (180x0,8x1,5=216)	mc	216
5	ACE08A1	Umplutura de nisip(180x0,8x0,3 =43,2)	mc	43,2
6	TSD01B1	Imprastierea pamantului cu lopata	mc	43,2
7	ACA11A2-asimilat	Montare teava PEHD Dn32mm	ml	13
8	ACA11B2-asimilat	Montare teava PEHD Dn63mm	ml	10
9	ACA11C1-asimilat	Montare teava PEHD Dn75mm	ml	88
10	ACE07A1	Spalarea si dezinfectarea conductelor PEHD D=32mm	ml	13
11	ACE07B1	Spalarea si dezinfectarea conductelor PEHD D=63mm	ml	10
12	ACE07B1	Spalarea si dezinfectarea conductelor PEHD D=75mm	ml	88
13	ACA11E3-asimilat	Tub PVC Dn 160	ml	40
14	ACD04B1-asimilat	Camin PVC Dn400	buc	5
15	ACD01J1	Rama cu capac carosabil	buc	5
16	TFE01A1-asimilat	Teava PE-Xa preizolata 75/140, SDR 11	ml	60
17	TFE02A1-asimilat	Cot PE-Xa, preizolat 75/140, SDR 11	buc	4
18	TFE05A1-asimilat	Caciula de capat pt teava 75/140	buc	4
19	TFE06C1-asimilat	Inel de etansare la trecerea prin zid la conducta 75/140	buc	4
20	IE03C1	Proba de etansare la presiune conducte	ml	60
21	IE04C1	Proba de functionare la cald conducte	ml	60
22	TFC01A1	Spalarea conductelor	ml	60
23	TRA06A10	Transportul betonului	t	36
24	TSD05A1	Compactare cu mai mecanic	100mc	2,16
25	TRA01A10	Transport pamant	t	216
26	TRB01C11	Transport pamant cu roaba	t	216
27	TRA01A1	Transport materiale prefabricate	t	1
28	ACE06A1	Sustineri cabluri si conducte	ml	10